

In connection with the renovation of Western Amphi, the quotations are invited from suitable and experienced persons for the works mentioned below.

1. **ALUMINUM FABRICATION** – Providing and fixing aluminum work (fixed) for windows and ventilators with extruded built up standard tubular sections/ appropriate sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete similar to the existing with Powder coated aluminum (minimum thickness of powder coating 50 micron) including providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. With float glass panels of 4.00 mm thickness: For fixed portion.

Approximate area 870Sqft

2. **ALUMINUM DOORS** – Providing and fixing aluminum work for doors with extruded built up standard tubular sections/ appropriate sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete similar to the existing with Powder coated aluminum (minimum thickness of powder coating 50 micron) including providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. With float glass panes of 6.00 mm thickness, door handles, lock, Auto close, Floor spring etc.

Quantity 5No's (Approximate area 170.1Sqft)

### **Terms & Conditions**

1. Any person/firm can quote more than one items related with Western Amphi renovation.
2. One contractor has to submit only one quotation for a particular item.

3. In case of tie, weightage will be given for their past experience in executing project inside college, license for undertaking Government projects, similar projects etc.
4. In the case of total contract an amount of 80% of material purchased for the work can be given as the interim payment of the work the remaining will be dispersed one or two stages up on completion based on the cost/nature of the work. The final disbursement will be given up on the completion of work.
5. 5% of the amount will keep as security for six months from the date of completion
6. For labour contract the disbursement will be on daily basis through the vouchers of alumni association
7. Material cost and labour cost should be quoted separately.

**Dead line of tender: 07/03/2018, 02.00 PM**

**Date of opening of tender: 08/03/2018, 04.00 PM**

For further queries, Contact,

1. Er. Sreejith Purushothaman, Mob - 9387444666
2. Er. P P Sivan, Mob – 9809631256
3. Er. Mohanan, Mob - 9447671828