

In connection with the renovation of Western Amphi, the quotations are invited from suitable and experienced persons for the works mentioned below.

1. **BRICK WORK& PLASTERING** - Solid Block Masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to Balcony floor level with thickness 20cm in : CM 1:6 etc complete and 12 mm thick plastering to the newly Constructed wall using cm 1:4. Brick work quantity Approximately 5m³ and Plastering area Approximately 25m²
2. **REPAIR OF EXISTING IRON WINDOWS-** Welding of existing window shutters to the existing window frames, Cutting of existing handles etc., Cleaning of window glass and supply and fixing of cooling film, Providing and applying two coats of enamel paint of approved quality and brand to the existing windows.(Window size – 1.3x 2.1m - 16No's)
3. **TILE WORK –**
 - a. Providing and fixing I st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make & color & size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. (Tile cost Rs 50/Sqft)
Approximate Area – 200sqft
 - b. Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622, of approved make in colors White, Ivory, Grey, fume Red Brown, laid on 20 mm thick cement mortar 1:4, including grouting the joints with white cement and matching pigments etc., complete. (Tile cost Rs 60/Sqft)
Approximate Area – 110sqft

Terms & Conditions

1. Any person/firm can quote more than one items related with Western Amphi renovation.
2. One contractor has to submit only one quotation for a particular item.
3. In case of tie, weightage will be given for their past experience in executing project inside college, license for undertaking Government projects, similar projects etc.
4. In the case of total contract an amount of 80% of material purchased for the work can be given as the interim payment of the work the remaining will be dispersed one or two

stages up on completion based on the cost/nature of the work. The final disbursement will be given up on the completion of work.

5. 5% of the amount will keep as security for six months from the date of completion
6. For labour contract the disbursement will be on daily basis through the vouchers of alumni association
7. Material cost and labour cost should be quoted separately.

Dead line of tender: 07/03/2018, 02.00 PM

Date of opening of tender: 08/03/2018, 04.00 PM

For further queries, Contact,

1. Er. Sreejith Purushothaman, Mob - 9387444666
2. Er. P P Sivan, Mob – 9809631256
3. Er. Mohanan, Mob - 9447671828