

In connection with the renovation of Western Amphi, the quotations are invited from suitable and experienced persons for the works mentioned below.

**1. ACOUSTIC SOUND ABSORBING PANELLING – As per the specification provided.- Heights – 6 m**

Acoustic wall Partition: An Acoustic wall partition with high quality acoustic treatment. . Acoustic wall providing glass wool (20kg/ cu.m and 25 mm) with one side Aluminium foil, fiber tissue, FULLTONE Acoustic (Gyproc) Tile 600x600mmx12.5mm in size fixed to Ceiling section channels (Truesteel, 300 mm C/C Vertical) fixed on steel frame work, joining and patching USG compound and fiber tape (as per manufactures recommendation min 2coat) and rubbing & finishing. For walls the Gypliner wall lining includes 13mm Gyproc Duraline board up to height of 1219mm has to be provided throughout the length (bottom line).

Approximate area 2200Sqft

**2. ACOUSTIC SOUND ABSORBING SUSPENDED CEILING – As per the specification provided.**

Acoustic Ceiling: False ceiling FULLTONE Gyproc Acoustic tile (600 mm×600 mm, 12.5 mm) acoustic Tile fixed to internal ceiling section (Truesteel) grid, joining and patching USG compound and fiber tape (as per manufactures recommendation min 2Coat) and rubbing & finishing. Ceiling grid providing perimeter channel section of the ceiling fixed to the wall. ‘L’ angles hang to the top of the roofing using soffit cleat at every 900x900mm square. The intermediate channels are laid in every 900mm c/c distance which is supported to ‘L’ angles. Ceiling sections are laid at every 300mm distance which fixed cross to intermediates by clips. The ceiling tiles are fixed to the ceiling section. Openable arrangements by using multiwood or other suitable material for the service of Ac indoor units (As recommended by AC suppliers) by should provide in the (back side) ceiling work.

Approximate area 2960Sqft

**Terms & Conditions**

1. Any person/firm can quote more than one items related with Western Amphi renovation.
2. One contractor has to submit only one quotation for a particular item.
3. In case of tie, weightage will be given for their past experience in executing project inside college, license for undertaking Government projects, similar projects etc.
4. In the case of total contract an amount of 80% of material purchased for the work can be given as the interim payment of the work the remaining will be dispersed one or two

stages up on completion based on the cost/nature of the work. The final disbursement will be given up on the completion of work.

5. 5% of the amount will keep as security for six months from the date of completion
6. For labour contract the disbursement will be on daily basis through the vouchers of alumni association
7. Material cost and labour cost should be quoted separately.

**Dead line of tender: 07/03/2018, 02.00 PM**

**Date of opening of tender: 08/03/2018, 04.00 PM**

For further queries, Contact,

1. Er. Sreejith Purushothaman, Mob - 9387444666
2. Er. P P Sivan, Mob – 9809631256
3. Er. Mohanan, Mob - 9447671828